

## APPENDIX D

## COST ESTIMATE OF PROPOSED RECORDS BUILDING

Building: Basement and one story; exterior of reinforced concrete walls; reinforced concrete flat slab frame (with monolithic floor finish); concrete masonry unit partitions; exposed concrete ceilings (painted); asphalt tile floor in offices and darkroom; cement finish elsewhere; fluorescent lighting throughout (secondary current); air conditioned with humidity control and forced air heat; security alarm system (no sprinklers); hydraulic elevator. Provisions for additional story. Contract to include installation of shelving furnished by Government.

Gross Area: Basement 10,320 sq. ft.  
1st Floor 10,970 " "  
Total 21,290 sq. ft.

Volume: Approximately 120,000 cu. ft.

E S T I M A T E

Construction	\$200,000
Air Conditioning and Heating	110,000
Fluorescent Lighting Fixtures	11,000
Electrical Work (Secondary Current)	33,000
Security Alarm	3,000
Plumbing	8,000
Elevator	10,000
Approaches	<u>10,000</u>

TOTAL ESTIMATED CONSTRUCTION COST 385,000

Contingencies	20,000
	<u>\$405,000</u>

Deduct from above for brick face with  
8-inch masonry unit backing. \$10,000

~~SECRET~~