

25X1A6a

CONVERSION OF [REDACTED],  
[REDACTED] TO RECORDS STORAGE

25X1A6d

A. Minimum building modifications

1. Increase interior light level, install exterior lighting, and miscellaneous connections to existing emergency power system, as required.
2. Modifications to secure roof and siding.
3. Modify door openings.
4. Door contact alarms and connection to annunciator in guard office; Detex clock stations; fire detection system.
5. Vinyl Asbestos flooring.
6. Install exhaust fan in existing louver.

B. CCTV System - Procure and Install

1. Five (5) motion detection systems.
2. Six (6) monitors (to be identical to those now installed at the station).
3. Install other related Government furnished items.

C. 18 000 cubic feet of shelving, procure and install.  
[REDACTED]