Declassifie	d in Part - Sanitized Copy Approved for Release 2012/04/24:CIA-RDP78B04747A0021000200	04-3
3		STATINTL
	27 March 1967	
	U. S. Government Washington, D. C.	
TATINTL	Attention:	
TATINTL	Subject: Proposal for design and fabrication of 40" x 40" Vacuum Easel for use on VG-894 Enlarger, and installation service.	
	Gentlemen:	
TATINITI	In response to your verbal request, we are pleased to quote the following:	
TATINTL TATINTL	One (1) Vacuum Easel for VG-894 Enlarger, in accordance with	
IAIINIL	Drawing #D-15997; to include fabrication of easel assembly,	
	mounting of easel on enlarger, and provision of a suitable vacuum generator. The price does not include any allowance for royalties for	
TATINTL	use of nor does it include any special provisions	
	for noise suppression of the vacuum generator exhaust noise.	
•	The basic construction will be as illustrated on our drawing. The proportions of the ball valves will be as suggested in the patent. The ball valves will be arranged in staggered rows 1/2" on centers both side-to-side and front to rear.	
TATINTL	Two industrial type vacuum cleaners are to be supplied to generate the required vacuum displacement and pressure differential.	
	The top surface of the easel is to be perforated steel sheet, .086" diam. holes on 9/64" staggered centers, and finished with a matte white surface. The top of the easel assembly is to be held flat within .008" total indicator reading. The steel surface will permit the use of magnetic paper locating devices. Installation includes adapting the three existing levelling jacks on the enlarger; levelling the easel with the enlarger bed; connecting the vacuum hoses to the easel and the	
T A TINIT!		
TATINTL		·

Declassified in	n Part - Sanitized Copy Approved for Release 2012/04/24 : CIA-RDP78B04747A0021000200	04-3
•		STATINTL
	-2-	
STATINTL	vacuum generators; and checking the units out after installation.	
	The price for the first unit is installed. This is made up of for materials and purchased parts, and 210 hours of manufacturing and installation labor.	STATINTL
	Delivery of this unit could be made in approximately 110 days under present schedules.	
	Terms are less 1% for 10-day payment; 1/2 of 1%, 20-day; net 30-day.	
•	We trust this proposal is satisfactory in all respects. If you need further details, please advise.	STATINTL
	Very truly yours,	

Enc: a/s

Declassified in Part - Sanitized Copy Approved for Release 2012/04/24 : CIA-RDP78B04747A002100020004-3

Page Denied